

**November
2018**

Pump House

Monthly Newsletter



Super Seal™ is an industry leading system safe sealant - its available NOW from Pump House



**Polymer
FREE**

Call +44(0)115 900 5858 for your prices or e-mail sales@pumph.co.uk



Keep your eyes wide open and stay tuned for our special Christmas Edition Newsletter which will be out on the 3rd of December.

It will be filled with Christmas fun and activities for your chance to win some sweet treats!



Line Clamps: Contractors' most favourite type of clamps



These lined universal pipe clamps are suitable for supporting all types of pipe work including **HVAC, boiler and drain**. They come with noise supressing rubber strips: 17dB(A) according to **ISO 3822-1**.

Code	Description	Nominal Bore (inch)	Dimensions (mm)			Max Working Load (N)	Quantity
			A	B	C		
X-PCL-12-14	Pipe Clamp Lined – 12-14mm	1/4	58	15	16	1000	Pack of 50
X-PCL-15-19	Pipe Clamp Lined – 15-19mm	3/8	62	18	16	1000	Pack of 50
X-PCL-20-25	Pipe Clamp Lined – 20-25mm	1/2	69	21	16	1000	Pack of 50
X-PCL-26-30	Pipe Clamp Lined – 26-30mm	3/4	74	23	16	1000	Pack of 50
X-PCL-32-36	Pipe Clamp Lined – 32-36mm	1	81	26	16	1000	Pack of 50
X-PCL-38-43	Pipe Clamp Lined – 38-43mm	1-1/4	87	30	16	1000	Pack of 50
X-PCL-44-49	Pipe Clamp Lined – 44-49mm	1-1/2	94	33	16	1000	Pack of 50
X-PCL-50-55	Pipe Clamp Lined – 50-55mm		103	36	16	1000	Pack of 50
X-PCL-56-61	Pipe Clamp Lined – 56-61mm	2	106	39	16	1000	Pack of 50
X-PCL-62-67	Pipe Clamp Lined – 62-67mm		113	42	16	1300	Pack of 50
X-PCL-68-73	Pipe Clamp Lined – 68-73mm		123	45	16	1300	Pack of 50
X-PCL-75-80	Pipe Clamp Lined – 75-80mm	1-1/2	128	48	16	1300	Pack of 50
X-PCL-82-86	Pipe Clamp Lined – 82-86mm		134	51	16	1300	Pack of 50
X-PCL-87-92	Pipe Clamp Lined – 87-92mm	3	141	54	16	1300	Pack of 50
X-PCL-95-102	Pipe Clamp Lined – 95-102mm	3-1/2	158	58	16	2150	Pack of 50
X-PCL-108-116	Pipe Clamp Lined – 108-116mm	4	170	65	18	2150	Pack of 25
X-PCL-121-127	Pipe Clamp Lined – 121-127mm		185	70	16	2150	Pack of 25
X-PCL-131-141	Pipe Clamp Lined – 131-141mm	5	195	77	16	2150	Pack of 25
X-PCL-159-163	Pipe Clamp Lined – 159-163mm		215	88	16	2150	Pack of 25
X-PCL-165-169	Pipe Clamp Lined – 165-169mm	6	226	91	16	2150	Pack of 25
X-PCL-192-202	Pipe Clamp Lined – 192-202mm		265	107	16	3000	Pack of 25
X-PCL-210-220	Pipe Clamp Lined – 210-220mm	8	274	117	16	3000	Pack of 25

Contact us for your prices and more information on +44(0)115 900 5858 or send us an email to sales@pumph.co.uk

Latest Case Study: Travelodge, East Grinstead

Products: Flexi heavy – Flexi QUAD
Services: Water Tank
Roof build-up: Warm roof design – PIR/PUR insulation with bituminous felt membrane



A **development** of a new 72-room Travelodge hotel on the Little King Street site in East Grinstead, was part of a £6.6 million redevelopment of the area around King Street on the old Caffyns site.

Pump House were asked to support a very heavy rooftop water tank at the above project, where the tank was of considerable weight. The operating weight of the tank,

(including contents - water) was nearly 13,000kg. By utilising secondary steelwork c/w our Flexi-heavy – Flexi QUAD support frameworks, Pump House could manage the very demanding imposed loads, uniformly back down through each foot in-turn. This resulted in low foot pressures exerted onto the waterproofing system beneath, to keep within the roof insulation boards permissible compressive strength limitations.

All frameworks are fully height adjustable, via the M24 adjuster legs to compensate flat roof falls, and steelwork is hot dip galvanised for durability, to BS EN ISO 1461:2009.



More information on our Flexi Website: <http://flexisupportsystems.co.uk/>



Watch our latest Flexi Video!

